



**Primo Group**

**Primo Group Services Pty Ltd**

**2/16 Bernera Rd**

**Prestons, NSW, 2170**

**ABN 82 160 390 269**

**[www.primogs.com.au](http://www.primogs.com.au)**

**[accounts@primogs.com.au](mailto:accounts@primogs.com.au)**

**02 8202 6006**

Issued On

18/9/2026

Proposal

Sydney Tech HS - Auditorium AV Upgrade

Proposal Number

6521

Project Location

Sydney Technical High School, 686 Forest Road Bexley NSW 2207,  
Bexley, NSW, 2207

Client Details

Sydney Technical High School

Tom Tran

[Tom.Tran8@det.nsw.edu.au](mailto:Tom.Tran8@det.nsw.edu.au)

02 8566 2600

686 Forest Road Bexley NSW 2207

Bexley NSW 2207

18/9/2026

Dear Tom Tr  n,

Thank you for the opportunity to present our proposal:

Sydney Tech HS - Auditorium AV Upgrade.

This document outlines the details of our proposal including scope of works, pricing, exclusions and notes.

If you require any further information, clarification or wish to discuss any elements of our proposal, please feel free to reach out to me.

We look forward to working together to deliver a high quality successful outcome for this project that exceeds expectations.

Regards,

Eric Jay Rolzhauser

Audio Visual Solutions Manager

[eric.rolzhauser@primogs.com.au](mailto:eric.rolzhauser@primogs.com.au)

02 8202 6006

0413 304 605

## SCOPE OF WORKS

### Auditorium Upgrade

The works will comprise a targeted upgrade of the existing auditorium AV system, including new control, audio processing, amplification, wireless microphone, video distribution and equipment rack infrastructure. Existing loudspeakers, active subwoofers, projector, motorised projection screen, lighting control system, hearing augmentation system and nominated existing cabling will be retained and integrated with the new equipment. The existing digital mixing console, digital stage I/O and stage input infrastructure will be replaced as part of the works. New cabling and supporting infrastructure will be provided where required to support the upgraded system.

The existing equipment rack will be replaced with a new 600 mm wide by 800 mm deep 27RU equipment rack installed in the same location. The rack will house the new audio processing, amplification, wireless microphone receiver, presentation switching, local music source, AV Line network switch, Dante to analogue audio interface, hearing augmentation interface and associated equipment. A rack mounted power distribution unit and four ventilation fans will be provided, with equipment installed and dressed to provide a serviceable and maintainable installation.

The existing control system will be replaced with a network based control system incorporating two 10" wall mounted touch panels, with one installed within the equipment rack and the second within the bio box. The rack touch panel will provide the control processor functionality, with both panels connected through the dedicated AV network infrastructure and initially configured as mirrored interfaces. A managed AV Line network switch will be provided within the equipment rack and uplinked to the client network.

Client network structured cabling, data outlets and associated network runs will be provided by the client or their nominated third party contractor. Dedicated point to point AV data cabling required between AV system components will be provided as part of these works.

The control system will provide dedicated Presentation and Performance modes. Presentation Mode will provide simplified control of presentation sources, projection, screen operation, installed audio, wireless microphones and nominated lighting scenes. Performance Mode will support deeper operation from the new performance audio console and retained lighting console while maintaining the required system processing and integration. Exact operating sequences, source defaults, audio controls, lighting recalls and interface layouts will be developed with the client during two included control workshops.

The existing lighting fixtures, lighting distribution equipment, network capable lighting rack controller, performance lighting console and DMX management equipment will be retained. The new control system will communicate with the existing lighting system over the client network to recall nominated scenes and playbacks already programmed within the lighting system. The existing lighting system will remain responsible for DMX and fixture control, with the existing network takeover arrangement between the permanent lighting controller and performance console retained.

A new 4x2 presentation matrix switching system will be supplied and installed. A rack mounted input plate will provide separate HDMI and USB C connections, with USB C supporting audio and video only without Power Delivery. A further HDMI and USB C input plate will be installed within the bio box. The client supplied ViVi wireless presentation device will also be integrated as a presentation source within the new system. Source selection will be manual from the touch panels, with the default startup source determined during the control workshops.

The presentation matrix will connect directly to the retained projector using HDBaseT. The retained projector is assumed to be fully operational. A dedicated backup HDMI input plate will also be provided and connected directly to the projector using a 30 m active optical HDMI cable, providing a direct presentation path that bypasses the primary presentation matrix switching system. The backup HDMI input will connect directly to the projector and will not provide an audio feed to the auditorium audio system. A replacement remote control will be supplied for the existing projector. The existing projector image will also be adjusted as required to improve alignment and presentation on the existing projection screen.

The existing motorised projection screen will be retained and a new Grandview IP control module will be supplied and installed to provide IP based integration with the new control system. The screen will operate automatically in conjunction with system and projector operation together with manual control from the touch panels.

A new 26x8 digital signal processor will provide the central audio mixing, routing, equalisation, crossover processing, delay, limiting, level control and system presets. The multimedia music source and presentation matrix audio will connect to the dedicated stereo inputs of the processor, maintaining the primary mic and line inputs for microphone and performance console integration. Final processing parameters will be established during commissioning to suit the retained loudspeakers, room acoustics and existing speaker circuit arrangement.

A new four channel digital wireless microphone system will provide three rechargeable handheld microphones and one rechargeable wireless lectern gooseneck microphone, together with a rack mounted four channel receiver, charging facilities and two directional remote antennas. The antennas will be installed at suitable high level positions on opposite sides of the auditorium, with final locations determined on site. All four wireless receiver channels will be connected to individual digital signal processor inputs and available for normal system operation.

The wireless microphone channels will connect directly to individual digital signal processor inputs, allowing them to operate independently of the performance mixing console. Individual level and mute control will be available from the touch panels, and the microphones will also be capable of feeding the foldback system. No microphone priority or automatic ducking will be applied.

The existing wired XLR lectern gooseneck microphone will be retained and integrated into a dedicated input of the digital signal processor. New fixed microphone cabling will be installed between the lectern microphone location and the AV system.

A rack mounted multimedia music input will also be provided for simple music playback without use of the performance console, providing Bluetooth audio, USB media playback and a physical analogue audio input. The multimedia source will be connected to a dedicated stereo input of the digital signal processor.

The existing digital mixing console, digital stage I/O unit and stage box will be replaced with a new Dante enabled digital performance mixing system. A new digital mixing console will be installed within the bio box and a new 16 input, 8 output Dante stage I/O unit will be installed within a new 5RU equipment rack at the stage. The console and stage I/O will communicate over the dedicated AV network using new point to point AV data cabling, providing remote stage input control and digital audio transport between the stage and bio box.

The new performance console will provide detailed live performance mixing. Main Left, Main Right and one common Foldback mix will be transported from the console over Dante to a four channel Dante to analogue interface located within the main equipment rack. Three analogue outputs from this interface will connect to dedicated digital signal processor inputs for Main Left, Main Right and Foldback, with the fourth analogue output retained as spare capacity.

Two new professional two channel power amplifiers will replace the existing auditorium amplifiers. The four available amplifier channels will serve the existing FOH loudspeaker pair, ceiling mounted delay loudspeaker pair, common foldback loudspeaker circuit and bio box loudspeaker. The bio box loudspeaker is assumed to be an approximately 240 watt low impedance loudspeaker.

All existing loudspeaker cabling will be retained and reused. As the exact loudspeaker models, impedance, power ratings and circuit topology are unknown, the existing speaker arrangement is assumed to be suitable for the proposed amplifier allocation. Final amplifier settings, loudspeaker equalisation, protection, output levels and delay alignment will be established during commissioning.

The two existing powered subwoofers will be retained and reinstated using new fixed balanced audio cabling. A dedicated XLR wall plate will be installed at each subwoofer location, together with two supplied XLR fly leads for connection between the wall plates and the retained powered subwoofers. The subwoofers will be tuned as part of final system commissioning and presented to the user as a single master subwoofer control.

The bio box loudspeaker will be provided with a dedicated processed output and will be capable of reproducing all system audio sources, including wireless microphones, presentation audio, local music playback and programme audio from the new performance console.

The existing Phonak Roger hearing augmentation system will be retained and integrated with the upgraded AV system. A new Roger Multimedia Hub will be provided and connected to a dedicated audio output from the digital signal processor, allowing nominated system programme audio to be distributed into the existing Roger hearing augmentation system.

All new control, signal and equipment connections not specifically identified for reuse will be provided as new cabling and labelled at the applicable termination points. Existing cabling identified for reuse will remain in place and will be functionally verified as part of final system commissioning. Dedicated point to point AV data cabling required for Dante, control and other AV specific device connections will be provided as part of the AV works. Client network structured cabling and network data runs will be provided by others.

Redundant legacy equipment associated with the upgraded control, video, audio processing and amplification systems will be removed, including the existing live mixing console, stage box and rack mounted digital stage I/O equipment being superseded by the new Dante performance audio system. All redundant cabling located beneath the stage will also be decommissioned and removed where accessible, together with associated redundant AV fixings and support hardware. Existing electrical cabling beneath the stage will remain in place and is specifically excluded from these decommissioning works.

Following installation, the complete system will be programmed, configured, tested and commissioned. Commissioning will include retained equipment and cabling verification, audio system tuning, loudspeaker and subwoofer integration, wireless microphone operation, wired lectern microphone integration, Dante audio transport, performance console and stage I/O operation, hearing augmentation audio integration, ViVi integration, backup HDMI operation, video switching, projection, projector image adjustment, new projection screen IP control, screen control, touch panel operation and integration with the retained lighting system. Final operating behaviour will reflect the outcomes of the two client control workshops and the practical performance of the retained equipment.

An optional bio box monitor output has been included, which will mirror the projector output if selected.

An optional camera recording and streaming system has been included, comprising a PTZ camera, dedicated recording and streaming encoder, audio balancing interface, RG6 video cabling terminated with BNC connectors and dedicated CAT6 F/UTP cabling. Programme audio will be provided from a dedicated digital signal processor output for recording and streaming use.

An optional audit of the existing theatrical lighting system has been included to assess the condition and operation of the existing lighting control and associated lighting infrastructure.

Separate optional 1.5 hour operation training sessions have also been included for the new Yamaha DM3 digital mixing console and the retained ChamSys QuickQ 20 lighting console. These sessions are additional to the standard AV system handover training included below.

## **Handover**

At project completion, a comprehensive handover package will be provided, including as built documentation, operations and maintenance manuals, and an asset register.

A 1 hour end user training session will also be conducted to ensure appropriate system operation and familiarity.

We will provide a 12 month defect liability period covering all workmanship associated with the installation and integration of the system. During this period, any defects arising from installation works will be rectified at no cost to the client.

All installation works will be carried out with attention to maintaining a clean and organized workspace. Rubbish will be removed from site upon completion, and the work area will be kept neat and tidy throughout the installation process.

## SUMMARY PRICING

|                    |             |
|--------------------|-------------|
| Auditorium Upgrade | \$69,185.90 |
| Subtotal (EX GST): | \$69,185.90 |
| Total GST Portion: | \$6,918.59  |
| Total (INC GST):   | \$76,104.49 |

Validity is thirty (30) calendar days from 16/9/2026 unless otherwise specified.

This proposal has been priced in Australian Dollars (AUD)

## OPTIONAL ITEMS

| Item                                                         | Part | Quantity | Price Each   | Price Total  |
|--------------------------------------------------------------|------|----------|--------------|--------------|
| Bio Box Monitor Output Plate                                 | -    | 1        | +\$766.05    | +\$765.56    |
| Stage Camera Including Recording & Streaming System          | -    | 1        | +\$11,455.16 | +\$11,455.16 |
| 1.5 Hour Yamaha DM3 Console Operation Training Session       | -    | 1        | +\$523.25    | +\$523.25    |
| 1.5 Hour Camsys QuickQ 20 Console Operation Training Session | -    | 1        | +\$523.25    | +\$523.25    |
| Half Day Lighting System Audit with Recommendations Report   | -    | 1        | +\$971.75    | +\$971.75    |

## DETAILED BILL OF MATERIALS

| Item                                                  | Part | Quantity | Price Each | Price Total |
|-------------------------------------------------------|------|----------|------------|-------------|
| Auditorium Upgrade                                    |      |          |            | \$69,185.90 |
| FOH Wall Mount Passive Speaker (Existing)             | OFE  | 2        | \$0.00     | \$0.00      |
| Delay Flying Passive Speaker (Existing)               | OFE  | 2        | \$0.00     | \$0.00      |
| Foldback Wall Mount Passive Speaker (Existing)        | OFE  | 2        | \$0.00     | \$0.00      |
| Bio Box Wall Mount Monitor Passive Speaker (Existing) | OFE  | 1        | \$0.00     | \$0.00      |
| Floor Powered Subwoofer (Existing)                    | OFE  | 2        | \$0.00     | \$0.00      |
| NEC PA653UL Laser Projector (Existing)                | OFE  | 1        | \$0.00     | \$0.00      |
| Projector Pole Mount (Existing)                       | OFE  | 1        | \$0.00     | \$0.00      |
| 200" 4.3m x 2.65m 16:10 Projection Screen (Existing)  | OFE  | 1        | \$0.00     | \$0.00      |
| Camsys QuickQ 20 Lighting Console (Existing)          | OFE  | 1        | \$0.00     | \$0.00      |
| Camsys QuickQ Rack Console (Existing)                 | OFE  | 1        | \$0.00     | \$0.00      |
| Lighting Bar (Existing)                               | OFE  | 1        | \$0.00     | \$0.00      |
| Lighting Fixture (Existing)                           | OFE  | 10       | \$0.00     | \$0.00      |
| ACME DMX Manager (Existing)                           | OFE  | 1        | \$0.00     | \$0.00      |
| Lectern XLR Gooseneck Microphone (Existing)           | OFE  | 1        | \$0.00     | \$0.00      |
| Phonak Roger Hearing Augmentation System (Existing)   | OFE  | 1        | \$0.00     | \$0.00      |

|                                                                                                                                                         |     |   |            |            |
|---------------------------------------------------------------------------------------------------------------------------------------------------------|-----|---|------------|------------|
| ViVi Wireless Presenter (Client Supplied)                                                                                                               | OFE | 1 | \$0.00     | \$0.00     |
| 27RU Equipment Rack 600x800<br>Including 4 x fans, 1 x shelf, 25 x cage nuts, 1 x horizontal 6 outlet PDU, 4 x castor wheels & levelling feet           | -   | 1 | \$1,504.43 | \$1,504.43 |
| 6RU 550mm Deep Swing Frame Cabinet Including 2 x fans, 1 x shelf, 10 x cage nuts                                                                        | -   | 1 | \$448.21   | \$448.21   |
| Two Channel Power Amplifier                                                                                                                             | -   | 2 | \$921.11   | \$1,842.22 |
| 26x8 Digital Signal Processor                                                                                                                           | -   | 1 | \$1,772.02 | \$1,772.02 |
| White 10.1" Wall Mount Touch Panel with Built In Control Processor                                                                                      | -   | 1 | \$4,248.00 | \$4,248.00 |
| White 10.1" Wall Mount Touch Panel                                                                                                                      | -   | 1 | \$3,303.60 | \$3,303.60 |
| 4x2 Video Matrix Switcher                                                                                                                               | -   | 1 | \$884.40   | \$884.40   |
| HDMI & USB-C Input Plate Transmitter                                                                                                                    | -   | 1 | \$633.60   | \$633.60   |
| HDMI & USB-C Input Plate                                                                                                                                | -   | 1 | \$106.01   | \$106.01   |
| 4 Channel Wireless Microphone System Including 3x Handheld Microphones, 1x Wireless Gooseneck Lectern Microphone, 2x Remote Antennae & Charging Station | -   | 1 | \$4,999.20 | \$4,999.20 |
| Audio Input Plate Including Bluetooth, USB & 3.5mm TRS AUX                                                                                              | -   | 1 | \$240.54   | \$240.54   |
| HDMI Input Plate (Direct to Projector)                                                                                                                  | -   | 1 | \$41.40    | \$41.40    |
| 30 Port Managed Network Switch 1G Ports 300W PoE+                                                                                                       | -   | 1 | \$2,156.04 | \$2,156.04 |
| 4 Output Dante Decoder                                                                                                                                  | -   | 1 | \$1,008.00 | \$1,008.00 |
| 16x8 Digital Stage Box with Dante                                                                                                                       | -   | 1 | \$1,842.92 | \$1,842.92 |

|                                                                                                                                                                                          |                  |   |             |             |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|---|-------------|-------------|
| Digital Mixing Console with Dante, 8 + 1 Fader Config, 16 mono + 1 stereo + 2 FX return input mixing channels, 16 Mic/Line (12 XLR + 4 XLR/TRS Phones Combo) inputs, and 8 (XLR) outputs | -                | 1 | \$2,552.02  | \$2,552.02  |
| Subwoofer Connection Wall Plate                                                                                                                                                          | -                | 2 | \$30.60     | \$61.20     |
| Phonak Roger Multimedia Hub                                                                                                                                                              | 052-3299         | 1 | \$627.60    | \$627.60    |
| Grandview IP Control Module End Caps                                                                                                                                                     | GV-GRIPENDCAPS   | 1 | \$166.34    | \$166.34    |
| Genuine Sharp/NEC Replacement Remote Control for PA653UL                                                                                                                                 | RD-480E/7N901322 | 1 | \$212.40    | \$212.40    |
| Cabling                                                                                                                                                                                  | CABLING          | 1 | \$1,976.72  | \$1,976.72  |
| Hardware & Consumables                                                                                                                                                                   | CONS             | 1 | \$2,880.00  | \$2,880.00  |
| Freight & Logistics                                                                                                                                                                      | FREIGHT          | 1 | \$540.00    | \$540.00    |
| Services                                                                                                                                                                                 | SERVICES         | 1 | \$35,139.60 | \$35,139.31 |

**Subtotal (EX GST): \$69,185.90**  
**Total GST Portion: \$6,918.59**  
**Total (INC GST): \$76,104.49**

## NOTES & ASSUMPTIONS

- We have assumed that parking will be made available at no charge for the duration of the project.
- We have assumed that unrestricted access to the site will be made available for the duration of the project during working hours.
- We have assumed that e-waste recycling is not required.
- We have assumed that the existing equipment being re-used is in working condition.
- We have assumed that the existing cabling being re-used is in working condition.
- We have assumed that rigging/engineering certification is not required.
- We have assumed that acoustic and fire sealing are not required.
- We have assumed there is no asbestos or other hazardous materials of relevance.
- We have allowed for de-commissioned equipment to be left on site for disposal by others unless disposal by PGS is preferred.
- We have allowed to run cabling through existing ceiling spaces, wall cavities and pathways where accessible.
- We have assumed that underground cabling, trenching, aerial cabling or external conduit are not required.
- We have allowed to decommission and remove all redundant cabling beneath the stage, excluding electrical cabling, together with associated redundant AV fixings and support hardware where practical and accessible.
  - Concealed or inaccessible redundant cabling that cannot reasonably be removed without building works or disruption to retained services may be left in place.
- We have assumed that the client will be responsible for any network configurations required on the client network.
  - We will provide guidance on what configurations are required.

- We have allowed for the touch panel, bluetooth input panel & HDMI/USB-C input panel to be housed within the equipment rack on a custom panel.
- We have allowed for two control workshop sessions to discuss the required control system scope and develop a suitable user interface to meet client expectations.
- We have assumed that the hall is suitable for an EWP to be used from a weight management of the floor perspective.
- We have allowed for floor coverings and protections for the use of the EWP.
- We have assumed that the two existing amplifiers are powering the front of house, delay, foldback and bio box monitor speakers in a four channel arrangement.
  - Based on this we have assumed that replacement amplifiers matching or exceeding the specifications of the existing amplifiers will be sufficient.
- We have allowed for AV control and network audio devices to operate through the dedicated AV Line network switch, with the switch uplinked to the client network
- We have assumed that all client network structured cabling, data outlets, patching and associated client network infrastructure will be provided by the client or their nominated third party contractor.
- We have assumed that a single common foldback audio mix will be sufficient.
- We have allowed to re-use the existing loudspeaker cabling serving the retained front of house, delay, foldback and bio box loudspeakers.
- We have allowed to provide new fixed balanced audio cabling and dedicated XLR wall plates for connection of the two retained powered subwoofers, together with new fly leads between the wall plates and subwoofers.
- We have allowed for final loudspeaker and subwoofer EQ, crossover, delay, limiting, output levels and other DSP parameters to be determined during commissioning to achieve the best practical system performance.
- We have allowed for the foldback speakers & bio-box loudspeaker to reproduce all system audio sources.

- We have allowed for the two active subwoofers to be commissioned as a pair and presented to the user as a single subwoofer master control, rather than two independent user controls.
- We have allowed for USB-C video and audio only, there is no power delivery from these ports.
- We have assumed that manual video input selection from the touch panel rather than automatic input switching is the preferred arrangement.
- We have assumed that the optional bio box monitor output will mirror the projector output, if included.
- We have assumed that the rack monitor output is not required.
- We have allowed for the projection screen to be automatically lowered and raised based on the power state of the projector, with a manual override from the touch panel.
- We have assumed that both the rack and bio box touch panels should be mirrors of each other.
- We have assumed that the Chamsys Quick Q 20 & Quick Q Rack are already connected permanently with the existing lighting systems and are configured with network takeover based on connectivity of the console.
- We have assumed that the lighting scenes and playbacks required for recall from the AV control system already exist within the existing lighting system. Creation or modification of advanced lighting programming is not included within the base scope.
- We have allowed for the new equipment rack to be located in the same position as the existing equipment rack, to allow for re-use of existing cabling where specified.
- We have allowed for new cabling only to be labelled.
- We have allowed for the necessary EWP for work at heights.
- We have allowed for the Yamaha DM3 digital mixing console to provide detailed live performance mixing when the system is operated in Performance Mode.
- We have allowed for a new Yamaha Tio1608-D2 Dante stage I/O unit to be installed within a new 5RU equipment rack at the stage and connected to the Yamaha DM3 over the dedicated AV network.

- We have allowed for the DM3 Main Left, Main Right and common Foldback feeds to be transported over Dante and converted to analogue within the main equipment rack for connection to the installed DSP.
- We have allowed to retain and integrate the existing wired XLR lectern gooseneck microphone into the new DSP system with new cabling.
- We have allowed to integrate the client supplied ViVi wireless presentation device as a presentation source within the new AV system.
- We have assumed that the client supplied ViVi device is fully operational, appropriately licensed and configured for use on the client network. Client account, licensing and network administration associated with the ViVi platform are by others.
- We have allowed for a dedicated backup HDMI input plate connected directly to the projector using a 30 m active optical HDMI cable, independently of the presentation matrix switching system.
- We have assumed that the direct projector backup HDMI input is intended as a contingency video connection and does not provide an audio feed to the installed auditorium audio system.
- We have allowed to integrate the existing Phonak Roger hearing augmentation system by providing a new Roger Multimedia Hub connected to a dedicated audio output from the DSP.
- We have assumed that the existing Phonak Roger Touchscreen Microphone, WallPilot, MyLink and associated hearing augmentation equipment are operational and compatible with the proposed Roger Multimedia Hub.
- Standard end user AV system training does not include detailed operation training for the Yamaha DM3 or ChamSys QuickQ 20 performance consoles. Separate 1.5 hour console operation training sessions have been provided as optional items.
- Where the optional recording and streaming system is selected, we have assumed that the client will provide the required network/internet access, streaming platform accounts, credentials and any associated subscriptions.

## EXCLUSIONS

No allowance has been made for the following unless explicitly detailed:

- Onboarding to new platforms requiring fees or subscriptions.
- Permits, approvals or applications requiring fees or subscriptions.
- Electrical requirements including supply, relocation, installation, upgrade or de-commission of:
  - Circuits & outlets.
  - Power conditioning & UPS.
  - Switchboards.
  - RCD/RCBO.
  - Incoming Power Supply.
- Electrical load or capacity assessment.
- Client network cabling & patching.
- Client network configurations.
- Formal certification of structured cabling is excluded. Dedicated AV data cabling provided under this scope will be functionally tested as part of AV system commissioning.
- Testing of structured cabling in excess of basic continuity testing.
- Building works including access panels, joinery, core holes, trenching, excavation, patching, painting & make good.
- Underground service location including Dial Before You Dig enquiries.
- Ventilation & cooling mechanisms.
- Cable pathways.
- Out of hours work (standard hours are Monday - Friday 7:00am-3:30pm).
- Project broken into multiple staged rollout.
- Data connections to devices which do not require a data connection for system functionality.
- Microsoft Teams, Zoom, CUCM or Webex licenses, profile creation or configuration.

- AV control integration with HVAC, house lighting, EWS or motorized blind systems.
- Floor or table box supply & Installation.
- Fire sealing of penetrations and cable pathways.
- Acoustic sealing of penetrations and cable pathways.
- BCA/DDA Hearing Augmentation compliance certification.
  - The scope is limited to providing an audio feed from the new AV system into the existing Phonak Roger hearing augmentation system via the new Roger Multimedia Hub.
- Repair or replacement of existing equipment being re-used.
- Troubleshooting or fault rectification of existing systems.
- Compatibility issues with client supplied or existing equipment.
- Slab or concrete scanning.
- Thermal imaging.
- Supply of fly leads for connection to wall plates.
- Certified rigging points.
- eWaste removal and recycling of existing equipment.
- Handling or removal of asbestos & other hazardous materials.
- Unforeseen site conditions that impact reasonable project works.
- Delays caused by third party disruption or restriction of access when and as required.
- Third party inspections or certifications of completed works.
- Parking charges.
- Acoustic modelling, sound pressure level design or intelligibility modelling.
- Configuration of advanced theatrical lighting show programming, complex cue stacks, production specific show files and ongoing event operation.
- Underground cabling, trenching, aerial cabling or external conduit
- New loudspeaker cabling serving the retained passive FOH, delay, foldback and bio box loudspeakers.
- Power delivery from USB-C inputs.

- Automatic input switching of connected video sources.
- Monitor output at the rack/stage.
- Monitor output at the bio box.
  - Unless optionally included.
- Configurations of lighting equipment.
- Cable tracing and labelling of existing cabling being re-used.
- Camera recording and streaming functionality is excluded from the base scope unless the optional recording and streaming system is selected.
  - Streaming platform subscriptions, accounts, credentials and associated fees are by the client.
  - Internet service, available bandwidth and client network configuration required for streaming are by the client or their nominated network provider.
- Migration, conversion or recreation of existing Midas M32R show files, scenes, presets or console programming onto the new Yamaha DM3 unless specifically detailed.
- Supply, licensing, account administration and client network configuration of the client supplied ViVi wireless presentation device.
- Detailed operational training for the Yamaha DM3 and ChamSys QuickQ 20 consoles beyond the standard AV system handover unless the respective optional console training session is selected.
- Repair, configuration, replacement or compliance certification of the existing Phonak Roger hearing augmentation equipment beyond integration of the new Roger Multimedia Hub with the AV system.
- Removal of electrical cabling under stage.
- Repair or servicing of the existing projector beyond supply and installation of the specified replacement lamp, supply of the replacement remote control and minor image adjustment detailed within the scope.
- Relocation or modification of the existing projector mounting arrangement.
- Repair or replacement of the retained motorised projection screen beyond installation and integration of the new IP control module.

## ACCEPTANCE & PAYMENT

Name: \_\_\_\_\_ Date: \_\_\_\_\_ Acceptance Signature: \_\_\_\_\_

### How to Pay

#### By Mail




Detach this section and mail your cheque to:

Primo Group Services Pty Ltd

Unit 2/16 Bernera Road


Prestons NSW 2170

#### By Credit Card



Credit Card Payments incur a 1.6% Financial Institution Surcharge and admin fee. Use the 'Pay Invoice' button to make a Credit Card payment.

#### By Direct Transfer



Primo Group Services Pty Ltd

NAB

BSB: 082 125

Account: 144580534



Reference:

Balance Due:

Due Date:

Account Terms -

This payment claim is made under the Building and Construction Industry Security Of Payments Act 1999 (NSW). Payment terms are available upon request.

### **Terms**

This claim is made under the building and construction payment security act of 1999

If any provision of these terms and conditions shall be invalid, void, illegal or unenforceable the validity, existence, legality and enforceability of the remaining provisions shall not be affected, prejudiced or impaired.

These terms and conditions and any contract to which they apply shall be governed by the laws of NSW and are subject to the jurisdiction of the courts of NSW

Primo Group Services Pty Ltd shall be under no liability whatever to the Customer for any indirect loss and/or expense (including loss of profit) suffered by the Customer arising out of a breach by Primo Group Services Pty Ltd of these terms and conditions.

In the event of any breach of this contract by Primo Group Services Pty Ltd the remedies of the Customer shall be limited to damages. Under no circumstances shall the liability of Primo Group Services Pty Ltd exceed the Price of the Works.

The Customer shall not be entitled to set off against or deduct from the Price any sums owed or claimed to be owed to the Customer by Primo Group Services Pty Ltd.

Primo Group Services Pty Ltd may license or sub-contract all or any part of its rights and obligations without the Customer's consent.

Primo Group Services Pty Ltd reserves the right to review these terms and conditions at any time. If, following any such review, there is to be any change to these terms and conditions, then that change will take effect from the date on which Primo Group Services Pty Ltd notifies the Customer of such change.

Neither party shall be liable for any default due to any natural disaster, war, terrorism, fire, flood, drought, storm or other event beyond the reasonable control of either party.

### **Acceptance**

Any instructions received by Primo Group Services Pty Ltd from the Customer for the supply of Works and/or the Customer's acceptance of Works undertaken by Primo Group Services Pty Ltd shall constitute acceptance of the terms and conditions contained herein.

Where more than one Customer has entered into this agreement, the Customers shall be jointly and severally liable for all payments of the Price.

Upon acceptance of these terms and conditions by the Customer, the terms and conditions are irrevocable and can only be rescinded in accordance with these terms and conditions or with the written consent of Primo Group Services Pty Ltd.

None of Primo Group Services Pty Ltd agents or representatives are authorised to make any representations, statements, conditions or agreements not expressed by the manager of Primo Group Services Pty Ltd in writing nor is Primo Group Services Pty Ltd bound by any such unauthorised statements.

### **Variations**

Anything not listed in the above scope of works is considered a variation

In the event that the Customer requests a variation all such requests shall be made in writing.

In the event that Primo Group Services Pty Ltd requests a variation, Primo Group Services Pty Ltd will, in writing; State the reason for the variation.

Provide a full description of the variation. State any effect the variation will have on the contract, including but not

limited to, the price, completion date and whether further permits or authorisations are required.

Other than for the events outlined in clause 3.4 and 3.5 Primo Group Services Pty Ltd shall obtain written acceptance by the Customer of any variation submitted by Primo Group Services Pty Ltd before commencing Work on the variation.

In the event of:

unforeseeable problems with the site which are only revealed when undertaking the works which Primo Group Services Pty Ltd considers should be rectified for the safe completion of the works.

Primo Group Services Pty Ltd being instructed to undertake extra works by any person authorised by the state or federal government: then Primo Group Services Pty Ltd may carry out any works needed to fix any such problem/s or carry out any such instructions. Any such additional works necessary are to be treated as a variation. However, if a price is not agreed upon then the Customer will be charged at Primo Group Services Pty Ltd actual cost-plus twenty percent (20%) for the works.

Primo Group Services Pty Ltd may by giving notice to the Customer at any time up to seven (7) days before delivery increase the price of the materials to reflect any increase in the cost to Primo Group Services Pty Ltd beyond the reasonable control of Primo Group Services Pty Ltd, (including, without limitation, foreign exchange fluctuations, taxes and duties, provisions of any Acts, By-Law, Order or Regulation of any parliament, municipality or local authority enacted after the date of contract between the Customer and Company and the cost of labour, materials and other manufacturing costs).

### **Price & Payment**

At Primo Group Services Pty Ltd sole discretion the price shall be either;

As indicated on invoices provided by Primo Group Services Pty Ltd to the Customer in respect of works or materials supplied; or

Primo Group Services Pty Ltd quoted price (subject to clause 3) which shall be binding upon Primo Group Services Pty Ltd provided that the Customer shall accept the Company's quotation in writing within thirty (30) days.

At Primo Group Services Pty Ltd sole discretion, a deposit may be required.

Primo Group Services Pty Ltd may submit a detailed payment claim at intervals not less than one month for work performed up to the end of each month. The value of work so performed shall include the reasonable value of authorised variations, whether or not the value of such variations has been finally agreed between the parties, and the value of materials delivered to the site but not installed.

Time for payment for the works shall be of the essence and will be stated on the invoice. If no time is stated, then payment shall be due seven (7) days following the date of the invoice.

Payment will be made by cash, or by cheque, or by bank cheque, or by direct credit, or by any other method as agreed to between the Customer and Primo Group Services Pty Ltd. The Price shall be increased by the amount of any GST and other taxes and duties which may be applicable, except to the extent that such taxes are expressly included in the building contract schedule.

### **Delivery of works**

Subject to clause 6.1 it is Primo Group Services Pty Ltd responsibility to ensure that the works start as soon as it is reasonably possible.

The works commencement date will be put back and the building period extended by whatever time is reasonable in the event that Primo Group Services Pty Ltd claims an extension of time (by giving the Customer written notice) where completion is delayed by an event beyond Primo Group Services Pty Ltd control, including but not limited to any failure by the Customer to:

- make a selection; or
- have the site ready for installation; or
- notify Primo Group Services Pty Ltd that the site is ready.

The works shall be deemed to be completed when the works carried out under this contract have been completed in accordance with the plans and specifications set out in this contract; and

The failure of Primo Group Services Pty Ltd to deliver shall not entitle either party to treat this contract as repudiated. Primo Group Services Pty Ltd shall not be liable for any loss or damage whatever due to failure by Primo Group Services Pty Ltd to deliver the works (or any of them) promptly or at all.

#### **Customer's Responsibility**

It is the intention of Primo Group Services Pty Ltd and agreed by the Customer that;

- any building/construction sites will comply with all NSW occupational health and safety laws relating to building/construction sites and any other relevant safety standards or legislation; and

Primo Group Services Pty Ltd is not responsible for the removal of rubbish from the building/construction site/s. This is the responsibility of the Customer.

#### **Risk**

If Primo Group Services Pty Ltd retains ownership of the materials nonetheless, all risk for the materials passes to the customer on completion.

#### **Title**

It is the intention of Primo Group Services Pty Ltd and agreed by the Customer that ownership of materials shall not pass until:

- the Customer has paid all amounts owing for the particular materials, and
- the Customer has met all other obligations due by the Customer to Primo Group Services Pty Ltd in respect of all contracts between Primo Group Services Pty Ltd and the Customer.

Receipt by Primo Group Services Pty Ltd of any form of payment other than cash shall not be deemed to be payment until that form of payment has been honoured, cleared or recognised and until then Primo Group Services Pty Ltd ownership or rights in respect of materials shall continue.

It is further agreed that:

- where practicable the materials shall be kept separate and identifiable until Primo Group Services Pty Ltd shall have received payment and all other obligations of the Customer are met; and
- until such time as ownership of the Materials shall pass from Primo Group Services Pty Ltd to the Customer Primo Group Services Pty Ltd may give notice in writing to the Customer to return the materials or any of them to Primo Group Services Pty Ltd. Upon such notice the rights of the Customer to obtain ownership or any other interest in the materials shall cease; and
- Primo Group Services Pty Ltd shall have the right of stopping the materials in transit whether or not delivery has been made; and
- if the Customer fails to return the Materials to Primo Group Services Pty Ltd then Primo Group Services Pty Ltd or Primo

Group Services Pty Ltd agent may enter upon and into land and premises owned, occupied or used by the Customer, or any premises as the invitee of the Customer, where the materials are situated and take possession of the Materials.

#### **Defects**

The Customer shall inspect the works on delivery and shall within thirty (30) days of delivery (time being of the essence) notify Primo Group Services Pty Ltd of any alleged defect, shortage in quantity, damage or failure to comply with the description or quote. The Customer shall afford Primo Group Services Pty Ltd an opportunity to inspect the works within a reasonable time following delivery if the Customer believes the works are defective in any way. If the Customer shall fail to comply with these provisions the works shall be presumed to be free from any defect or damage. For defective Works, which Primo Group Services Pty Ltd has agreed in writing that the Customer is entitled to reject, Primo Group Services Pty Ltd liability is limited to either (at Primo Group Services Pty Ltd discretion) replacing the works or repairing the Works.

#### **Returns**

Primo Group Services Pty Ltd may (in its discretion) accept the return of materials for credit but this may incur a handling fee of ten percent (10%) of the value of the returned materials plus any freight.

#### **Warranty**

To the extent required by statute subject to the conditions of warranty set out in clause 12.1 Primo Group Services Pty Ltd warrants that if any defect in any workmanship of Primo Group Services Pty Ltd becomes apparent and is reported to Primo Group Services Pty Ltd within twelve (12) months of the date of delivery (time being of the essence) then Primo Group Services Pty Ltd will either (at Primo Group Services Pty Ltd sole discretion) replace or remedy the workmanship. The conditions applicable to the warranty given by clause 12.1 are:

The warranty shall not cover any defect or damage which may be caused or partly caused by or arise through:

- Failure on the part of the Customer to properly maintain any works; or
- Failure on the part of the Customer to follow any instructions or guidelines provided by Primo Group Services Pty Ltd ; or
- Any use of any works otherwise than for any application specified on a quote or order form; or
- The continued use of any works after any defect becomes apparent or would have become apparent to a reasonably prudent operator or user; or
- Fair wear and tear, any accident or natural disaster.

The warranty shall cease and Primo Group Services Pty Ltd shall thereafter in no circumstances be liable under the terms of the warranty if the workmanship is repaired, altered or overhauled without Primo Group Services Pty Ltd consent.

In respect of all claims Primo Group Services Pty Ltd shall not be liable to compensate the Customer for any delay in either replacing or remedying the workmanship or in properly assessing the Customer's claim.

For material not manufactured by Primo Group Services Pty Ltd the warranty shall be the current warranty provided by the manufacturer of the Material. Primo Group Services Pty Ltd shall be under no liability whatsoever except for the express conditions as detailed and stipulated in the manufacturer's warranty.

The Commonwealth Trade Practices Act 1974, Building Act 1993, and Fair-Trading Acts

Nothing in this agreement is intended to have the effect of contracting out of any applicable provisions of the Commonwealth Trade Practices Act 1974, Building Act 1993, or the Fair-Trading Acts in each of the States and Territories of Australia, except to the extent permitted by those Acts where applicable.

#### **Default & Consequences of Default**

Interest on overdue invoices shall accrue from the date when payment becomes due daily until the date of payment at a rate of 2.5% per calendar month and such interest shall compound monthly at such a rate after as well as before any judgement.

If the Customer defaults in payment of any invoice when due, the Customer shall indemnify Primo Group Services Pty Ltd from and against all costs and disbursements incurred by Primo Group Services Pty Ltd in pursuing the debt including legal costs on a solicitor and own client basis and the Company's collection agency costs.

Without prejudice to any other remedies Primo Group Services Pty Ltd may have, if at any time the Customer is in breach of any obligation (including those relating to payment) Primo Group Services Pty Ltd may suspend or terminate the supply of Works to the Customer under the Building and Construction Industry Security of Payments Act 2002. Primo Electrical Services Pty Ltd will not be liable to the Customer for any loss or damage the Customer suffers because Primo Group Services Pty Ltd exercised its rights under this clause.

If any account remains overdue after thirty (30) days, then an amount of the greater of \$20.00 or 10.00% of the amount overdue (up to a maximum of \$200) shall be levied for administration fees which sum shall become immediately due and payable.

Without prejudice to Primo Group Services Pty Ltd other remedies at law Primo Group Services Pty Ltd shall be entitled to cancel all or any part of any order of the Customer which remains unperformed and all amounts owing to Primo Group Services Pty Ltd shall, whether or not due for payment, become immediately payable in the event that:

any money payable to Primo Group Services Pty Ltd becomes overdue, or in Primo Group Services Pty Ltd opinion the Customer will be unable to meet its payments as they fall due; or  
the Customer becomes insolvent, convenes a meeting with its creditors or proposes or enters into an arrangement with creditors, or makes an assignment for the benefit of its creditors; or  
a receiver, manager, liquidator (provisional or otherwise) or similar person is appointed in respect of the Customer or any asset of the Customer.

#### **Cancellation**

Primo Group Services Pty Ltd may cancel any contract to which these terms and conditions apply or cancel delivery of works at any time before the works are delivered by giving written notice to the Customer. On giving such notice Primo Group Services Pty Ltd shall repay to the Customer any sums paid in respect of the Price. Primo Group Services Pty Ltd shall not be liable for any loss or damage whatever arising from such cancellation.

In the event that the Customer cancels delivery of works the Customer shall be liable for any loss incurred by Primo Group Services Pty Ltd (including, but not limited to, any loss of profits) up to the time of cancellation.

#### **Privacy Act 1988**

The Customer agrees for Primo Group Services Pty Ltd to obtain from a credit reporting agency a credit report containing personal credit information about the Customer in relation to credit provided by Primo Group Services Pty Ltd.

The Customer agrees that Primo Group Services Pty Ltd may exchange information about the Customer with those credit providers either named as trade referees by the Customer or named in a consumer credit report issued by a credit reporting agency for the following purposes:

to assess an application by Customer; and/or  
to notify other credit providers of a default by the Customer; and/or

to exchange information with other credit providers as to the status of this credit account, where the Customer is in default with other credit providers; and/or

to assess the credit worthiness of Customer.

The Customer consents to Primo Group Services Pty Ltd being given a consumer credit report to collect overdue payment on commercial credit (Section 18K(1)(h) Privacy Act 1988).

The Customer agrees that personal credit information provided may be used and retained by Primo Group Services Pty Ltd for the following purposes and for other purposes as shall be agreed between

the Customer and Company or required by law from time to time:

provision of Works; and/or

marketing of Works by Primo Group Services Pty Ltd, its

agents or distributors in relation to the Works; and/or

analysing, verifying and/or checking the Customer's credit, payment and/or status in relation to provision of Works;

and/or

processing of any payment instructions, direct debit facilities and/or credit facilities requested by Customer;

and/or

enabling the daily operation of Customer's account and/or the collection of amounts outstanding in the Customer's account in relation to the Works.

Primo Group Services Pty Ltd may give information about the Customer to a credit reporting agency for the following purposes:

to obtain a consumer credit report about the Customer;

and/or

allow the credit reporting agency to create or maintain a credit information file containing information about the Customer.

#### **Rates**

Day rate 7am – 5pm

Standard call out - minimum 4 hours charge per man and hourly rate apply. In case we need materials and the supplier is not open, we will do a temporary job to restore power and make it safe.

Further work will be carried out when materials are available.

#### **Acceptance of Quote**

Trusting that you are completely satisfied with this proposal, I am pleased to inform you that we have the staff and resources to commence at your convenience.

To accept the quotation, please complete details under acceptance & payment. Alternatively, Primo Group Services Pty Ltd will accept a digital copy via email.